

|                                                                                                               |  |              |               |
|---------------------------------------------------------------------------------------------------------------|--|--------------|---------------|
| <b>A/C &amp; Ductwork – Quote Sheet</b>                                                                       |  | OWNER        | Jeff Loewen   |
| 301 S Aztec Drive, White House, TN 37188 · 1,400 sq ft, 3 bed / 2 bath · package unit + complete new ductwork |  | PREPARED     | 9 Sep 2026    |
|                                                                                                               |  | QUOTES       | 3 contractors |
|                                                                                                               |  | FIRST VISITS | Thu 10 Sep    |

⚠ **Page 1 is the job** — hand it over or read from it. Page 2 is the eleven questions — read from it. Pages 3–5 are one answer sheet per contractor, already named, so the numbers actually compare.

1 THE JOB

7 SUPPLIES · 1 RETURN

|                   |                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|-------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| REMOVE            | Remove and dispose of the existing <b>Nordyne R4GD-030K072C</b> package unit — 2.5 ton, 72,000 BTU gas, <b>R-22</b> , approx. 2007.                                                                                                                                                                                                                                                                                             |
| SET & CONNECT     | Set the new gas/electric package unit on the <b>existing concrete pad</b> . New gas connector with shutoff and sediment trap, safety disconnect, whip, and <b>breaker change 40 A → 25 A</b> . Natural gas — <b>no LP conversion</b> .                                                                                                                                                                                          |
| DUCTWORK          | <b>Complete replacement</b> . Fabricated sheet-metal supply and return plenums at the unit, new insulated branches to all <b>seven registers</b> , and the <b>single central return</b> in the living room.                                                                                                                                                                                                                     |
| THE DEFECT TO FIX | Both the main supply trunk and the return run down the centre of the house and are <b>twisted where they meet the unit</b> — original to the house. The builder ran the duct first, then rotated it to meet the equipment instead of making a proper transition. <b>Every cubic foot of air in the house passes through those two points</b> . The 2007 installer had the system apart and left it. <b>Do not repeat that</b> . |
| OWNER'S ROLE      | Jeff wires his own house and is comfortable in the panel. He is willing to work alongside on the ductwork. <b>Quote it both ways if that changes your number</b> .                                                                                                                                                                                                                                                              |

2 EQUIPMENT — TWO ACCEPTABLE PATHS

2.5 TON IS SETTLED

| PATH                                                                                              | UNIT                                                                                                                                                                       | OWNER'S COST |
|---------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|
| <b>A · Owner supplies</b><br>Contractor installs, or inspects & starts up an owner-installed unit | <b>Blueridge BRP7GE1330E054P-01A</b><br>2.5 ton cool · 54,000 BTU in / 44,000 out · 13.4 SEER2 · 81% AFUE · <b>R-454B</b> with on-board leak detection · AHRI 217109080    | \$3,123      |
| <b>B · Contractor supplies</b><br>State the exact model and the equipment price separately        | Equivalent <b>2.5 ton</b> gas/electric package unit, <b>13.4 SEER2 or better, A2L refrigerant</b> (R-454B or R-32).<br>Comparable Goodman retails <b>\$4,645–\$4,715</b> . | quote it     |

**Sizing is settled and is not open:** the existing data plate reads **030 — 2.5 ton**, which has run this 1,400 sq ft house for years. A 3 ton would oversize it and hurt humidity removal. Confirm with a **Manual J**, do not assume upward.

3 NUMBERS YOU WILL NEED ON SITE

VERIFIED FROM BOTH DATA PLATES

| ITEM                       | EXISTING (NORDYNE)      | NEW (BLUERIDGE)                               |
|----------------------------|-------------------------|-----------------------------------------------|
| Cooling / heat             | 2.5 ton · 72,000 BTU in | 2.5 ton · 54,000 in / 44,000 out              |
| Refrigerant                | R-22<br>phased out      | <b>R-454B</b> (A2L)                           |
| Min ampacity / max breaker | 25.0 A / <b>40 A</b>    | 17.5 A / <b>25 A</b>                          |
| Cabinet W × D × H          | 47.5 in (side)          | 47.66 × 47.66 × 40.89 · 400 lb                |
| Pad                        | existing                | spec 50 × 53 — <b>measure before delivery</b> |
| Supply opening             | —                       | side 13.44 × 14.32 · btm 14.02 × 11.49        |
| Return opening             | —                       | side 13.44 × 17.07 · btm 16.77 × 11.49        |
| Gas connection             | —                       | 1/2 in · natural gas                          |

**Openings are rectangular, so the plenum IS the square-to-round transition** — no separate adapters needed. Round takeoff collars land the branches on the plenum face.

|                                                                                                                                                                                                                                                                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>GOOD SIGNS</b> <ul style="list-style-type: none"><li>Measures the house — <b>does a real Manual J</b> rather than matching the old unit</li><li>Talks about <b>the return</b> and grille free area, not just the supply side</li><li>Brings up <b>static pressure</b> without being asked</li><li>Willing to <b>itemise</b> equipment and labour</li><li>Already <b>tooled for A2L</b> and says so plainly</li></ul> | <b>PUSH BACK ON</b> <ul style="list-style-type: none"><li>“You need <b>3 ton</b>” with no load calculation</li><li>A <b>lump sum</b> with no equipment/labour split</li><li>Reusing the <b>twisted</b> trunk connection — that is the defect being paid to fix</li><li>A <b>hard start kit</b> on a brand-new compressor</li><li>Any <b>cover or canopy</b> over the unit — top discharge plus a gas flue; the manual forbids it</li><li>An <b>R-410A</b> unit — no longer legal to install</li></ul> |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Benchmarks for judging a quote: duct replacement runs **\$25–\$55 per linear foot** (\$35–\$55 around Nashville); a full system with new ductwork in this market runs **\$8,000–\$13,000**. Contractors typically mark materials up **2.5×–3.5×** wholesale at a 35–45% install margin — that margin funds the labour warranty, the callback and the A2L tooling.  
Working file and full sources: docs/hvac/ac\_unit\_and\_ductwork\_2026-08-31.md

**01 Do you install PACKAGE units? Gas/electric, everything outside on a slab.**

Many residential shops mainly do split systems. This is the fastest disqualifier – ask it first.

**02 Are you trained and tooled for A2L refrigerant – R-454B and R-32?**

New for 2026. R-410A can no longer be installed. A2L gauges, recovery machines and leak detectors run \$5,000–\$10,000 per truck, so this answer separates who has invested.

**03 Will you install a unit I supply – or inspect and start up one I install, certified to ACCA Quality Installation?**

The manufacturer's warranty accepts equipment *installed or certified* by a qualified installer. Either answer works; "no" to both means path B.

**04 Will you fabricate sheet-metal supply AND return plenums at the unit?**

This is the whole job – it is what removes the twist. Flex pulled onto a collar is not an answer.

**05 Will you provide Manual J, Manual S and Manual D in writing?**

Not a favour – ACCA Quality Installation is a written **condition of the equipment warranty**.

**06 Will you record static pressure before and after, and give me the numbers?**

Turns "it breathes better" into a measurement. Also part of ACCA QI.

**07 Is complete duct replacement in this quote – 7 supply branches and the central return?**

In or out. If out, say what it would add.

**08 Gas connection, the 40 A → 25 A breaker change, and permits – included? Who pulls them?**

White House has enforced the 2021 ICC Mechanical Code since 1 Jan 2025. Codes Dept: 615-672-4350 ext 2120.

**09 How long is your LABOUR warranty?**

The manufacturer covers parts only – never labour. A contractor labour warranty is real money. One local firm advertises **10 years parts and labour**; use that as the benchmark.

**10 How soon can you start, and how long will you be on site?**

Lead time is the reason this went out to quote at all.

**11 Itemise EQUIPMENT separately from LABOUR – and quote labour-only as an alternate.**

A lump sum hides the split. The gap between your turnkey and labour-only price is the equipment markup, stated by you.

CONTRACTOR

Petitt Heating & Cooling

615-654-0814 · 127 Raymond Hirsch Pkwy, White House · est. 2010

VISIT

Thu 10 Sep – AM

|    |                                             |  |
|----|---------------------------------------------|--|
| 01 | Package units? (gas/electric, all outside)  |  |
| 02 | A2L tooled – R-454B and R-32?               |  |
| 03 | Install my unit – or certify one I install? |  |
| 04 | Fabricate BOTH plenums, supply + return?    |  |
| 05 | Manual J / S / D in writing?                |  |
| 06 | Static pressure before AND after?           |  |
| 07 | All duct incl. the central return?          |  |
| 08 | Gas + 40 A → 25 A + permits? Who pulls?     |  |
| 09 | Labour warranty – how many years?           |  |
| 10 | Start date, and days on site?               |  |
| 11 | Equipment itemised apart from labour?       |  |

| REP ON SITE                               | MOBILE / EMAIL |
|-------------------------------------------|----------------|
| LICENCE # · VERIFY.TN.GOV                 | EARLIEST START |
| TN-64284                                  |                |
| A EQUIPMENT – MODEL: -----                |                |
| B DUCTWORK – COMPLETE REPLACEMENT         |                |
| C ELECTRICAL, GAS, PERMITS                |                |
| D LABOUR                                  |                |
| LABOUR-ONLY ALTERNATE (I SUPPLY THE UNIT) |                |
| TOTAL, INSTALLED                          |                |

CONTRACTOR

Daniels Heating & Air

(615) 804-1078 · 2880 Gideon Rd, Greenbrier · est. 1988, third generation

VISIT

Thu 10 Sep – AM

|    |                                             |  |
|----|---------------------------------------------|--|
| 01 | Package units? (gas/electric, all outside)  |  |
| 02 | A2L tooled – R-454B and R-32?               |  |
| 03 | Install my unit – or certify one I install? |  |
| 04 | Fabricate BOTH plenums, supply + return?    |  |
| 05 | Manual J / S / D in writing?                |  |
| 06 | Static pressure before AND after?           |  |
| 07 | All duct incl. the central return?          |  |
| 08 | Gas + 40 A → 25 A + permits? Who pulls?     |  |
| 09 | Labour warranty – how many years?           |  |
| 10 | Start date, and days on site?               |  |
| 11 | Equipment itemised apart from labour?       |  |

| REP ON SITE                               | MOBILE / EMAIL |
|-------------------------------------------|----------------|
|                                           |                |
| LICENCE # · <a href="#">VERIFY.TN.GOV</a> | EARLIEST START |
|                                           |                |
| A EQUIPMENT – MODEL: -----                |                |
| B DUCTWORK – COMPLETE REPLACEMENT         |                |
| C ELECTRICAL, GAS, PERMITS                |                |
| D LABOUR                                  |                |
| LABOUR-ONLY ALTERNATE (I SUPPLY THE UNIT) |                |
|                                           |                |
| TOTAL, INSTALLED                          |                |

CONTRACTOR

Derryberry's Heat & Air

615-452-8121 · 212 N Water Ave, Gallatin · est. 1986 · NATE · TVA Quality Contractor

VISIT

To be confirmed

|    |                                             |  |
|----|---------------------------------------------|--|
| 01 | Package units? (gas/electric, all outside)  |  |
| 02 | A2L tooled – R-454B and R-32?               |  |
| 03 | Install my unit – or certify one I install? |  |
| 04 | Fabricate BOTH plenums, supply + return?    |  |
| 05 | Manual J / S / D in writing?                |  |
| 06 | Static pressure before AND after?           |  |
| 07 | All duct incl. the central return?          |  |
| 08 | Gas + 40 A → 25 A + permits? Who pulls?     |  |
| 09 | Labour warranty – how many years?           |  |
| 10 | Start date, and days on site?               |  |
| 11 | Equipment itemised apart from labour?       |  |

|                                           |                |
|-------------------------------------------|----------------|
| REP ON SITE                               | MOBILE / EMAIL |
| <hr/>                                     | <hr/>          |
| LICENCE # · <a href="#">VERIFY.TN.GOV</a> | EARLIEST START |
| <hr/>                                     | <hr/>          |
| A EQUIPMENT – MODEL: -----                | <hr/>          |
| B DUCTWORK – COMPLETE REPLACEMENT         | <hr/>          |
| C ELECTRICAL, GAS, PERMITS                | <hr/>          |
| D LABOUR                                  | <hr/>          |
| LABOUR-ONLY ALTERNATE (I SUPPLY THE UNIT) | <hr/>          |
| <hr/>                                     | <hr/>          |
| TOTAL, INSTALLED                          | <hr/>          |