

REQUEST FOR QUOTE · PREPARED BY THE HOMEOWNER

A/C Changeout & Complete Ductwork

301 S Aztec Drive, White House, TN 37188 · 1,400 sq ft, 3 bed / 2 bath

Jeff Loewen

Prepared 9 September 2026



Derryberry's Heat & Air

TOBY "NOSE" COMFORT

Derryberry's Heat & Air

615-452-8121 · Gallatin · est. 1986

SITE VISIT

Thu 10 Sep · 8-10 AM

THE WORK

REMOVE	Existing Nordyne R4GD-030K072C package unit — 2.5 ton, 72,000 BTU gas, R-22 , approx. 2007. Haul away.
SET	New gas/electric package unit on the existing pad . Gas connector with shutoff and sediment trap, disconnect, whip. Natural gas — no LP conversion.
DUCTWORK	Complete replacement . Fabricated sheet-metal supply and return plenums at the unit, new insulated branches to all seven registers , and the single central return in the living room.
THE DEFECT	Both trunks run down the centre of the house and are twisted where they land on the unit — original to the house. Every cubic foot of air passes through those two points. The 2007 changeout left it in place. That is the part I am paying to fix.
MY PART	I do my own electrical and will work alongside on the duct. If that changes your number, quote it both ways.

SPECIFICATIONS

Sizing	2.5 ton — data plate reads 030. Confirm by Manual J.
Unit I can supply	Blueridge BRP7GE1330E054P-01A · 54,000 in / 44,000 out · 13.4 SEER2 · R-454B · AHRI 217I09080 \$3,123 delivered — Alpine Home Air, freight included, in stock
Electrical	old MCA 25.0 A / max 40 A → new 17.5 A / max 25 A
Cabinet & pad	47.66 × 47.66 × 40.89 in, 400 lb · pad spec 50 × 53 (existing carries 47.5 in)
Supply opening	side 13.44 × 14.32 · bottom 14.02 × 11.49
Return opening	side 13.44 × 17.07 · bottom 16.77 × 11.49
Gas / permits	1/2 in, natural gas · White House enforces 2021 ICC Mechanical · Codes 615-672-4350 x2120

WHAT THE QUOTE NEEDS TO COVER

SCOPE	Package changeout plus complete duct replacement — seven supplies, the central return, and fabricated plenums on both sides at the unit. All in your number?
REFRIGERANT	Are you set up for A2L — R-454B and R-32?
SIZING & PROOF	Manual J to confirm the tonnage, and static pressure before and after — I want the numbers.
EQUIPMENT	I can supply the unit myself. Will you install it, or certify the install ? Otherwise quote yours — model and price.

ELECTRICAL, GAS, PERMIT	New unit drops the breaker from 40 A to 25 A . You handling that, the gas connection, and the permit?
THE QUOTE	Equipment itemised apart from labour , plus a labour-only figure if I supply the unit. Labour warranty term and earliest start date.

Openings are rectangular, so the **fabricated plenum is the square-to-round transition** — no separate adapters. Branches land on the plenum face with round takeoff collars. **R-410A equipment can no longer be installed.**

REP ON SITE	MOBILE / EMAIL	LICENCE # · VERIFY.TN.GOV	EARLIEST START DATE
A EQUIPMENT — MODEL: _____	_____	C ELECTRICAL, GAS, PERMITS	_____
B DUCTWORK — COMPLETE REPLACEMENT	_____	D LABOUR · WARRANTY _____ YRS	_____
LABOUR-ONLY ALTERNATE (I SUPPLY THE UNIT)	_____	TOTAL, INSTALLED	_____

Written quote requested. Duct replacement in this market runs \$25-\$55 per linear foot; a full system with new ductwork runs \$8,000-\$13,000 installed.